18: 1200 (Part VI) - 1974

(Reaffirmed 1987)

Indian Standard

METHOD OF MEASUREMENT OF BUILDING AND CIVIL ENGINEERING WORKS

PART VI REFRACTORY WORK

(Second Revision)

Fourth Reprint JULY 1988 (Incorporating Amendment No. 1)

UDC 69.003.12:666.76

© Copyright 1980

BUREAU OF INDIAN STANDARDS MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG NEW DELHI 110002

Indian Standard

METHOD OF MEASUREMENT OF BUILDING AND CIVIL ENGINEERING WORKS

PART VI. REFRACTORY WORK

(Second Revision)

Civil Works Measurement Sectional Committee. BDC 44

Chairman

SHRI V. R. VAISH

Members

SHRI N. P. ACHARYYA ASSISTANT ADVISER (PHE) SHRI B. G. BALIEKAR SHRI P. L. BHASIN CHIEF ENGINEER, HEADQUARTERS CHIEF ENGINEER (R & B)

SUPERINTENDING ENGINEER (R & D) (Alternate) SHRI R. K. CHOUDHRY SHRI I. P. PURI (Alternate) SHRI W. J. DAGAMA

SHRI V. B. DESAI DIRECTOR, IRI DIRECTOR (RATES & COSTS) DEPUTY DIRECTOR (RATES & COSTS) (Alternate)

SHRI P. K. DOCTOR SHRI D. S. VIJAYENDRA (Alternate) SHRI I. DURAI RAI EXECUTIVE ENGINEER (PLANNING & Designs). Northern RAILWAY SHRI P. N. GADI

SHRI V. G. HEGDE SHRI J. P. SHARMA (Alternate) SHRI G. V. HINGORANI

Rebresenting

Bureau of Public Enterprises, Ministry of Finance

The Commissioner for the Port of Calcutta Ministry of Health & Family Planning Vijavnagar Steel Project Institute of Surveyors, New Delhi Heavy Engineering Corporation Ltd, Ranchi Public Works Department, Government of Andhra Pradesh

Bhakra Management Board, Nangal Township

Bombay Port Trust Hindustan Construction Co Ltd. Bombay Irrigation Department, Government of Uttar Pradesh Central Water & Power Commission, New Delhi

Concrete Association of India, Bombay

Hindustan Steelworks Construction Limited, Calcutta Ministry of Railways

Institution of Engineers (India), Calcutta National Buildings Organization, New Delhi

Gammon India Ltd, Bombay

(Continued on page 2)

@ Copyright 1990 BUREAU OF INDIAN STANDARDS

This publication is protected under the Indian Copyright Act (XIV of 1957) and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

IS: 1200 (Part VI) - 1974

(Continued from page 1) Members Representing SHRI H. K. KHOSLA Irrigation Department, Government of Haryana SHRI KRISHAN KUMAR Ministry of Shipping & Transport (Roads Wing) SHRI K. K. MADHOK Builders Association of India, Bombay SHRI MUNISH GUPTA (Alternate) SHRI DATTA S. MALIK Indian Institute of Architects, Bombay PROF M. K. GODBOLE (Alternate) Éngineer-in-Chief's Branch, Army Headquarters, SHRI R. S. MURTHY New Delhi SHRI V. V. SASIDARAN (Alternate) SHRI T. S. MURTHY National Project Construction Corporation, New Delhi SHRI K. N. TANEJA (Alternate) SHRI C. B. PATEL M. N. Dastur & Co Pvt Ltd, Calcutta SHRI B. C. PATEL (Alternate) Metallurgical & Engineering Consultants (India) SHRI A. A. RAJU Limited, New Delhi SHRI K. G. SALVI Hindustan Housing Factory Ltd, New Delhi SHRI G. B. SINGH (Alternate) SECRETARY Central Board of Irrigation and Power, New Delhi DEPUTY SECRETARY (I) (Alternate) DR R. B. SINGH Banaras Hindu University, Varanasi

SHRI S. SRINIVASAN Hindustan Steel Ltd, Ranchi SUPERINTENDING SURVEYOR OF Central Public Works Department (Aviation). Works (Aviation) SURVEYOR OF WORKS (I) ATT-

ACHED TO SSW (AVIATION) (Alternate) SUPERINTENDING SURVEYOR OF

Central Public Works Department, New Delhi

Works (I) SURVEYOR OF WORKS (I)

ATTACHED TO SSW (I) (Alternate)

TECHNICAL EXAMINER

Buildings and Communication Department, Government of Maharashtra

SHRI D. AIITHA SIMHA, Director (Civ Engg) Director General, BIS (Ex-officio Member)

Secretary

New Delhi

SHRI K. M. MATHUR

Deputy Director (Civ Engg), BIS

Indian Standard METHOD OF MEASUREMENT OF BUILDING AND CIVIL ENGINEERING WORKS PART VI REFRACTORY WORK

(Second Revision)

O. FOREWORD

- 0.1 This Indian Standard (Part VI) (Second Revision) was adopted by the Indian Standards Institution on 8 February 1974, after the draft finalized by the Civil Works Measurement Sectional Committee had been approved by the Civil Engineering Division Council.
- **0.2** Measurement occupies a very important place in the planning and execution of any civil engineering work from the time of first estimates to the final completion and settlement of payments for a project. Methods followed for measurement are not uniform and considerable differences exist among practices followed by different construction agencies and also among various Central and State Government departments. While it is recognized that each system of measurement has to be specifically related to administrative and financial oranizations within a department responsible for the work, a unification of various systems at technical level has been accepted as very desirable specially as it permits a wider range of operation for civil engineering contractors and eliminates ambiguities and misunderstanding of various systems followed.
- 0.3 Among various civil engineering items, measurement of buildings was the first to be taken up for standardization and this standard having provisions ralating to building work was first published in 1958 and was revised in 1964. In the course of usage of this standard by various construction agencies in the country, several clarifications and suggestions for modifications were received and as a result of study, the technical committee responsible for this standard decided that its scope besides being applicable to buildings should be expanded to cover method of measurement of civil engineering works like industrial and river valley projects.
- 0.4 Since different trades are not related to one another, the Sectional Committee decided that each trade as given in IS: 1200-1964* shall be issued separately as a different part. This will also be helpful to users in using the specific standard. This part covers method of measurement of refractory work.

^{*}Method of measurement of building works (revised).

IS: 1200 (Part VI)- 1974

0.5 For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a measurement, shall be rounded off in accordance with IS: 2-1960* The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard.

1. SCOPE

1.1 This standard (Part VI) covers the method of measurement of refractory work.

2. GENERAL RULES

- 2.1 Clubbing of Items Items may be clubbed together provided that the break up of the clubbed items is agreed to be on the basis of the detailed description of the items stated in this standard.
- 2.2 Booking of Dimensions In booking dimensions, the order shall be consistent and generally in the sequence of length, breadth or width and height or depth or thickness.
- 2.3 Measurement Unless otherwise stated hereinafter all work shall be measured net in the decimal system, as fixed in place, as given in 2.3.1 to 2.3.4.
 - 2.3.1 Dimensions shall be measured to the nearest 0.01 m.
 - 2.3.2 Areas shall be worked out to the nearest 0.01 m².
 - 2.3.3 Cubic contents shall be worked out to the nearest 0.01 m³.
 - 2.3.4 Weight shall be worked out to the nearest 0.001 tonne.
- 2.4 Description of Items The description of each item shall, unless otherwise stated be deemed to include, where necessary, conveyance, delivery, handling, unloading, storing waste, return of packing, necessary scaffoldings, platforms, walkways, tools and tackles, stacking item wise, opening of packages and disposal of wood, straw etc. This shall also include use of necessary equipments, safety appliances, lighting at place of work, ventilation facilities, where necessary.
- 2.5 Waste All measurement of cutting shall, unless otherwise stated, be deemed to include consequent wastage.
- 2.6 Deduction Where a minimum area is defined for the deduction of opening voids or both, such area shall refer only to openings or voids within the space measured.

^{*}Rules for rounding off numerical values (revised).

- 2.7 Work to be Measured Separately The refractory work to be carried out in hot conditions shall be so specified indicating range of temperature and work shall be measured separately.
- 2.8 Bills of Quantities The bills of quantities shall fully describe the materials and workmanship and accurately represent the work to be executed.

3. METHOD OF MEASUREMENT

- 3.1 The items of work wherever necessary and unless otherwise stated shall be deemed to include the following:
 - a) Dressing of the bricks/blocks including cutting, grinding and chipping to achieve proper thickness of joint and alignment as required in the drawings for all classes of work.
 - b) Dressing of bricks/blocks including cutting, grinding and chipping wherever necessary for expansion joints, sliding joints, binding joints, etc, to ensure proper curvature and keying in arches, curved surface, etc.
 - c) Forming of expansion joints, sliding joints, etc, excluding filling (for filling see 3.8).
 - d) Finishing, pointing, clearing and cleaning of masonry joints, gaps, hollows, cavities, opening passages, ducts etc.
- 3.2 The refractory and insulation bricks and blocks, types of mortars and powders to be used shall be fully described. Other auxiliary and filling materials, such as paper, cardboard, asbestos materials, mineral wool, water glass, coke pitch, carbon mass, special sands, crumbs, powders, admixtures and plasticizers required to be incorporated in the works shall also be described.
- 3.3 All refractory work unless otherwise specified shall be measured in cubic metres. The measurement shall be inclusive of mortar joints, expansion joints and sliding joints. Deductions for voids, openings, etc, shall be made only when the area of each such opening and voids exceeds 0.01 square metre.
- 3.4 The method of measurement on volumetric basis as specified in 3.3 shall also apply for castable refractory work or refractory concreting, rammed mass filling; filling of loose insulation materials, such as mica crumbs, slag wools, asbestos powders, fireclay mass and carbon mass.
- **3.5** Where the brick/blocks lining is separated from the shell or wall surface by the use of asbestos, cardboard, etc, such insulating material shall be fully described and measured separately in square metres.
- 3.6 Where insulation plaster is applied over the refractory surface, the same shall be fully described and measured separately in square metres.

IS: 1200 (Part VI) - 1974

- 3.7 Refractory grout work shall be fully described and measured in cubic metres on the basis of theoretical volume to be grouted.
- 3.8 Filling of expansion joints, sliding joints with paper, cardboard, etc, shall be fully described and measured separately in running square metres.
- 3.9 Unless otherwise stated fixing of anchors, hangers and supporting steel members for the refractory brickwork shall be separately measured [see IS: 1200 (Part VIII) 1974*].
- 3.10 Unless otherwise stated painting of finished masonry with cement or fireclay mortars, water glass, etc, shall be measured saparately [see IS: 1200 (Part XIII) 1971†].

^{*}Method of measurement of building and civil engineering works: Part VIII Steel work and iron work (third revision) •

[†]Method of measurement of building and civil engineering works: Part XIII Plastering and pointing (second revision).

BUREAU OF INDIAN STANDARDS

Headquarters :	
Manak Bhavan, 9 Bahadur Shah Zafar Marg,	NEW DELHI 110002
Telephones: 3 31 01 31, 3 31 13 75	Telegrams: Manaksanstha
	(Common to all Offices)
Regional Offices :	Telephone
*Western ; Manakalaya, E9 MIDC, Marol, Ar BOMBAY 400093	ndheri (East). 6 32 92 95
†Eastern: 1/14 C. I. T. Scheme VII M, V. I. Maniktola, CALCUTTA 700054	P. Road, 36 24 99
Northern: SCO 445-446, Sector 35-C CHANDIGARH 160036	{2 18 43 3 16 41
Southern: C. I. T. Campus, MADRAS 60011	₹ 41 25 19
Branch Offices :	(41 29 16
Pushpak,' Nurmohamed Shaikh Marg, Khanp	£2.00.49
AHMADABAD 380001	our, {2 63 48 2 63 49
'F' Block, Unity Bldg, Narasimharaja Square BANGALORE 560002	
Gangotri Complex, 5th Floor, Bhadbhada Ro BHOPAL 462003	oad. T. T. Nagar. 6 27 16
Plot No. 82/83, Lewis Road, BHUBANESHV	VAR 751002 5 36 27
53/5 Ward No. 29, R. G. Barua Road, 5th Byelane, GUWAHATI 781003	_
5-8-56C L. N. Gupta Marg, (Nampally Static HYDERABAD 500001	on Road), 22 10 83
R14 Yudhister Marg, C Scheme, JAIPUR 30	2005 \[\begin{cases} 6 34 71 \\ 6 98 32 \end{cases} \]
117/418B Sarvodaya Nagar, KANPUR 2080	
Patliputra Industrial Estate, PATNA 800013	6 23 05
Hantex Bldg (2nd Floor), Rly Station Road TRIVANDRUM 695001	52 27
Inspection Office (With Sale Point):	
Institution of Engineers (India) Building, 1332 Shivaji Nagar, 5 24 35 PUNE 410005	
*Sales Office in Bombay is at Novelty Chamber Bombay 400007	rs, Grant Road, 89 65 28
†Sales Office in Calcutta is at 5 Chowringhee Appl Street, Calcutta 700072	roach. P. O. Princep 27 68 00

AMENDMENT NO. 2 MAY 1986

TO

IS:1200(Part 6)-1974 METHOD OF MEASUREMENT OF BUILDING AND CIVIL ENGINEERING WORKS PART 6 REFRACTORY WORK

(Second Revision)

[Page 5, clause 3.1(d)] - Add the following at the end:

'for up to 0.1 m² each (see 3.3)'.

(BDC 44)

Reprography Unit, BIS, New Delhi, India